

# SHT Improvements Achieve Early Implementation on VCS

**Status:** Implemented (Partial Implementation)

## PROBLEM / OBJECTIVE

Improving the design, manufacturing and application of Special Hull Treatment (SHT) on Virginia class submarines (VCS) can reduce installation and maintenance costs. SHT is installed via a bond-in-place (tile) or mold-in-place process, depending upon the location on the hull. The Navy Metalworking Center (NMC) led a ManTech project to evaluate several improvement areas to reduce cost and enhance performance.

## ACCOMPLISHMENTS / PAYOFF

### **Process Improvement:**

Electric Boat Corporation (EB) reviewed the bond-in-place installation process and materials and identified the following areas for further investigation:

- Improve tile manufacturing processes to reduce cost and rework
- Modify tile features to aid in installation
- Improve installation materials and processes to reduce installation time and increase reliability
- Enhance manufacturing process for multi-layer tile

The project team established requirements, identified candidate processes and materials, performed multi-staged technical evaluations, and generated a cost-savings analysis to verify that project metrics were being met.

### **Implementation and Technology Transfer:**

Among the project results, EB provided recommendations to minimize material waste by casting to near-net thickness and increasing the number of stock tile sizes used to machine the final tile shapes. EB partially implemented near-net thickness molding on VCS tiles in the fourth quarter of FY15, achieving a material savings of \$229,000 per hull, with a potential for a total of \$440,000 per hull savings with full implementation. In addition, the VCS Program Office (PMS 450) has accepted the project-developed assembly process for multi-layer tile, which will be used to procure the tile for the large-scale mock-up and ship test patch.

This article was prepared by the Navy Metalworking Center, operated by Concurrent Technologies Corporation, under Contract N00014-10-D-0062 to the Office of Naval Research as part of the Navy ManTech Program. Approved for public release; distribution is unlimited.

S2562 Improved Tiling Systems  
Rev A (JUN16)



Improving SHT tile manufacturing and application processes will reduce cost and increase reliability while in service. (U.S. Navy photo)

### **Expected Benefits and Warfighter Impact:**

Improvements to materials and/or installation processes will lower the cost to manufacture the tile, decrease installation labor and rework, lower overall installation time, and improve reliability. These savings include \$440K per hull to cast tile to near-net thickness and an additional \$125K per hull to create additional stock tile sizes. If PMS 450 successfully completes the alternative seam filler configuration, then an estimated \$135K per hull can be avoided at Post Shakedown Availability and \$450K can be avoided at each of the four Extended Dry-docking Selected Restricted Availabilities, due to increased durability of the SHT system. Results of this project will also benefit the Ohio Replacement Program (PMS 392), which will save an estimated \$848K per hull by casting tile to near-net thickness and creating additional stock sizes.

## TIME LINE / MILESTONE

Start Date: March 2014  
End Date: November 2015

## FUNDING

Navy ManTech Investment: \$1.2M

## PARTICIPANTS

PMS 450  
PMS 392  
NSWCCD  
EB  
NMC  
ONR Navy ManTech